BRUHAT BANGALORE MAHANAGARA PALIKE

Name of Work: Construction of Drains and providing grills at BB Road in Kempegowda Ward No-01

MODIFIED SCHEDULE-B

Sl. No.	Description of Item	Unit	Qty	Rate	
				In Fig.	In Words
1	Earthwork excavation for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications	Cum	0.00	589.11	Rupees Five Hundred Eighty Nine And Paise Eleven Only
2	Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications.	Cum	0.00	6152.06	Rupees Six Thousand One Hundred Fifty Two And Paise Six Only
3	Providing and laying in position reinforced cement concrete of design Mix M25 with OPC @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintels and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, lintles, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM curing, complete but excluding cost of reinforcement as per specifications.	Cum	0.00	7265.39	Rupees Seven Thousand Two Hundred Sixty Five And Paise Thirty Nine Only
4	Providing T.M.T steel reinforcement for R.C.C work TMT bars Fe500 including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications.	Tonne	0.00	88249.32	Rupees Eighty Eight Thousand Two Hundred Forty Nine And Paise Thirty Two Only

Executive Engineer
Bruhat Bangalaru Mahanagara Palike
Yelahanka, Division

Sl. No.	Description of Item	Unit	Qty	Rate	
				In Fig.	In Words
5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications.	Sqm	0.00	330.34	Rupees Three Hundred Thirty And Paise Thirty Four Only
6	Fabricating, providing and erecting in positiort of MS Hot Dip Galvanised Sq. Hallow Poles of 132 X 132 Heavy gauge of length 3000mm with MS. Hot dip Galvanised grill work as per approved design and drawing of chief architect. Using 12 X 75mm galvanised flat or alriound frame and 20 X 20mm galvanised forged design with square for vertical at 150mm c/c as shown in the drawing including providing forged ornamental arrow head at top and bottom. The work is inclusive of throughing flat, square rods, placing welding all the joints, including grinding, finishing 2 coats of anticorrosive paint over one coat of metal primer. The rate is inclusive of all materials like MS. Hollow galvanized pipe, flats, forged square rods, cost of labour for all items of work cost painting, welding, cutting, grinding with all lead and lift as per specification including loading and unloading with cost and conveyance of all materials, labour, machinery andincidental charges for the successful completion of the work as per the direction of the Engineer-in- charge of the work. (Data Rate)	Sqm	243.60	9578.49	Rupees Nine Thousand Five Hundred Seventy Eight And Paise Forty Nine Only
7	Providing and fixing stainless steel 304 grade for staircase railings, balconies, ramps, with hand rail, 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20m regular intervals and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of and electrical charges, etc., complete as per specifications.	Sqm	339.60	6811.56	Rupees Six Thousand Eight Hundred Eleven And Paise Fifty Six Only
8	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3	Cum	134.60		

Executive Engineer
Brihat Bengaluru Mahanagara Palike
Yelahanka, Division

Sl. No	Description of Item	Unit	Qty	Rate	
				In Fig.	In Words
	Quantity Upto 125%		126.75	225.51	Rupees Two Hundred Twenty Five And Paise Fifty One Only
	Quantity Above 125%		7.85	225.51	Rupees Two Hundred Twenty Five And Paise Fifty One Only
9	Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications. MORTH / Chapter 3	Sqm	841.49	6.66	Rupees Six And Paise Sixty Six Only
10	Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of modified proctors density. MORTH Specification No. 305	Cum	334.30	360.86	Rupees Three Hundred Sixty And Paise Eighty Six Only
11	Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.	Cum	84.15	2096.34	Rupees Two Thousand Ninety Six And Paise Thirty Four Only
12	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. MORTH Specification No. 2100	Cum	126.22	5950.42	Rupees Five Thousand Nine Hundred Fifty And Paise Forty Two Only

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

Sl. No.	Description of Item	Unit	Qty	Rate	
				In Fig.	In Words
13	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum,Coarse and fine aggregate conforming to IS:383-2016, with Superplastizer at 3 lts conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints,including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine, and curing including cost of all materials, labour,hire charges of machineries,all lead & lift charges etc., complete as per specifications. -do- with OPC at 360 kg/cum and coarse aggregate 0.69cum, fine aggregate 0.46cum.	Cum	128.16	5901.90	Rupees Five Thousand Nine Hundred One And Paise Ninety Only
	Quantity Upto 125%		126.75	5901.90	Rupees Five Thousand Nine Hundred One And Paise Ninety Only
	Quantity Above 125%		1.41	5901.90	Rupees Five Thousand Nine Hundred One And Paise Ninety Only
14	Providing and laying bituminous concrete 40mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 507 of MORTH V revision as per IRC SP-53-2015. – do – using 40-60 TPH capacity HMP with mechanical paver grading II (30-45mm) with 5.4 % of modified bituminus binder consisting of 4.97% of VG-30 bitumen (60/70 grade) and 0.43% of plastomeric thermoplastics (waste plastic)	Cum	0.00	8950.53	Rupees Eight Thousand Nine Hundred Fifty And Paise Fifty Three Only

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division

Sl. No.	Description of Item	Unit	Qty	Rate	
				In Fig.	In Words
	EIRL-ITEMS				
E-1	Providing precast slab of 100 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge Data Rate	Sqm	13.50	2448.01	Rupees Two Thousand Four Hundred Forty Eight And Paise One Only
E-2	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete.(KPWD SR 2018-19, Page No.27, Item No.5.30)	Nos	33.00	453.02	Rupees Four Hundred Fifty Three And Paise Two Only
E-3	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 (KPWD SR 2018-19, Page No.180, Item No.24.1)	Sqm	5.25	88.83	Rupees Eighty Eight And Paise Eighty Three Only

Executive Engineer
Yelahanka Division
BBMP

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division